



Addendum No. 1
Little Chicago Road Pipe Rehabilitation (EN-302)

September 17, 2018

Item #1 – Clarifications

The following clarifications supersede any specifications within the contract information book.

1. The pond on the upstream end can be lowered by up to 24 inches below the existing top of structure at the Contractor's expense. The use of pumping is permitted. The existing structure cannot be altered or modified and shall remain water tight at the completion of the project. For example, the structure cannot be cut or cored.
2. Both 36" lines were video inspected in August 2018 so the pre-construction video can be waived. Here are links to the videos:
 - a. https://www.dropbox.com/s/w5h1w66u0ueu9la/EN-302%20LCR%20Pipe%20vid%201_ST-SOHARB-4100_ST-SOHARB-4000.mp4?dl=0
 - b. https://www.dropbox.com/s/a9f4n7b9yz6c6w0/EN-302%20LCR%20Pipe%20vid%201_ST-SOHARB-4100_ST-SOHARB-4050.mp4?dl=0
3. The City will provide one post construction video inspection after the completion of the work by the Contractor at no cost to the Contractor. If that video inspection determines any repairs or remedies are required, future video inspections are the responsibility of the Contractor and at no cost to the Owner. Video shall be equivalent pre-construction video included above.

Please acknowledge receipt of this Addendum by sending an email to jhellmann@noblesville.in.us

CITY OF NOBLESVILLE

James J. Hellmann, P.E. – Assistant City Engineer